City of Tempe

BID DATE 3/17/05

Project No. 3200031

Curry Road Waterline - Scottsdale Road to Stadem Drive

BID TIME: 10:00 A.M.

Base Bid

Item No.	Item Name	Quantity	Unit	Eng. Est. Unit Cost / Total Cost	ACHEN-GARD Unit Cost / Total Cost	ARCHON, INC. Unit Cost / Total Cost	PIERSON CON Unit Cost / Total Cost	B & F CONTRA Unit Cost / Total Cost
1	42" Waterline and Fittings, Furnish and Install	3645	LF	$300.00	$259.00	$330.00	$315.00	$431.40
				$1,093,500.00	$944,055.00	$1,202,850.00	$1,148,175.00	$1,572,453.00
2	12" DIP Waterline and Fittings, Furnish & Install (Restrained Joints)	514	LF	$100.00	$314.00	$165.00	$205.00	$160.00
				$51,400.00	$161,396.00	$84,810.00	$105,370.00	$82,240.00
3	8" DIP Waterline and Fittings, Furnish & Install (Restrained Joints)	273	LF	$90.00	$228.00	$130.00	$208.00	$100.00
				$24,570.00	$62,244.00	$35,490.00	$56,784.00	$27,300.00
4	Miller Road Valve Vault "E" (Sta 69+02), Furnish & Install	1	LS	$68,400.00	$128,353.00	$120,000.00	$78,000.00	$94,700.00
				$68,400.00	$128,353.00	$120,000.00	$78,000.00	$94,700.00
5	Stadem Drive Vault "F" (Sta 81+80), Furnish & Install	1	LS	$69,075.00	$113,287.00	$120,000.00	$75,000.00	$91,430.00
				$69,075.00	$113,287.00	$120,000.00	$75,000.00	$91,430.00
6	42" Butterfly Valve and Access Manhole (Sta 45+80), Furnish & Install	1	LS	$21,000.00	$34,778.00	$50,000.00	$38,000.00	$58,230.00
				$21,000.00	$34,778.00	$50,000.00	$38,000.00	$58,230.00
7	12" Gate Valve Furnish & Install	33	EA	$1,200.00	$1,914.00	$2,000.00	$1,400.00	$1,300.00
				$39,600.00	$63,162.00	$66,000.00	$46,200.00	$42,900.00
8	8" Gate Valve Furnish & Install	8	EA	$900.00	$781.00	$1,000.00	$800.00	$910.00
				$7,200.00	$6,248.00	$8,000.00	$6,400.00	$7,280.00
9	6" Gate Valve Furnish & Install	6	EA	$700.00	$469.00	$800.00	$700.00	$470.00
				$4,200.00	$2,814.00	$4,800.00	$4,200.00	$2,820.00
10	Valve Box and Cover, MAG Std. Det. 391-1-C. Per T-115, Furnish & Install	47	EA	$250.00	$433.00	$300.00	$350.00	$375.00
				$11,750.00	$20,351.00	$14,100.00	$16,450.00	$17,625.00
11	Debris Cap, Including Locator Coil, MAG Std Det 392-A	47	EA	$150.00	$120.00	$150.00	$100.00	$85.00
				$7,050.00	$5,640.00	$7,050.00	$4,700.00	$3,995.00
12	Flushing Fire Hydrant, Furnish & Install	5	EA	$3,700.00	$1,848.00	$2,500.00	$2,500.00	$1,800.00
				$18,500.00	$9,240.00	$12,500.00	$12,500.00	$9,000.00

13	Remove 30" and Larger Diameter Waterline	2490	LF	$25.00	$6.00	$15.00	$12.00	$26.00
				$62,250.00	$14,940.00	$37,350.00	$29,880.00	$64,740.00
14	Water Service Relocation (Complete) per Tempe Det. T-212	14	EA	$2,500.00	$2,434.00	$700.00	$2,500.00	$1,000.00
				$35,000.00	$34,076.00	$9,800.00	$35,000.00	$14,000.00
15	Pipe Plugs, MAG Std Det 427, Furnish & Install	4	EA	$600.00	$901.00	$500.00	$800.00	$1,600.00
				$2,400.00	$3,604.00	$2,000.00	$3,200.00	$6,400.00
16	Concrete Encasement MAG Std Det 404, Furnish & Install	165	LF	$70.00	$155.00	$150.00	$85.00	$85.00
				$11,550.00	$25,575.00	$24,750.00	$14,025.00	$14,025.00
17	Concrete Sidewalk Tempe Det T-345, Remove and Replace	2210	SF	$10.00	$12.00	$10.00	$5.00	$17.00
				$22,100.00	$26,520.00	$22,100.00	$11,050.00	$37,570.00
18	Curb & Gutter MAG Std Det. 220, Type A, Remove & Replace	250	LF	$20.00	$34.00	$30.00	$25.00	$27.00
				$5,000.00	$8,500.00	$7,500.00	$6,250.00	$6,750.00
19	Single Curb MAG Std 222, Type A, Remove & Replace	660	LF	$15.00	$29.00	$30.00	$24.00	$22.00
				$9,900.00	$19,140.00	$19,800.00	$15,840.00	$14,520.00
20	Asphalt Concrete Pavement Section A-A, Tempe Det T-450, Remove & Replace	685	SY	$50.00	$68.00	$30.00	$30.00	$100.00
				$34,250.00	$46,580.00	$20,550.00	$20,550.00	$68,500.00
21	Asphalt Concrete Pavement Section B-B, Tempe Det T-450, Remove & Replace	8482	SY	$65.00	$20.00	$25.00	$22.00	$23.00
				$551,330.00	$169,640.00	$212,050.00	$186,604.00	$195,086.00
22	Communication Conduits, Furnish & Install	2485	LF	$8.00	$20.00	$15.00	$27.00	$23.50
				$19,880.00	$49,700.00	$37,275.00	$67,095.00	$58,397.50
23	18" Storm Drain With Slot Inlet and Catch Basin, Tempe Det T-354 and MAG Std Det 534-2 Type E,	1	LS	$6,250.00	$9,575.00	$23,925.00	$11,000.00	$10,000.00
				$6,250.00	$9,575.00	$23,925.00	$11,000.00	$10,000.00
24	Storm Water Pollution Prevention Plan	1	LS	$25,000.00	$15,990.00	$2,000.00	$5,000.00	$2,600.00
				$25,000.00	$15,990.00	$2,000.00	$5,000.00	$2,600.00
25	Remove and Salvage Fire Hydrant	2	EA	$2,500.00	$1,068.00	$500.00	$2,000.00	$260.00
				$5,000.00	$2,136.00	$1,000.00	$4,000.00	$520.00
26	Traffic Control	1	LS	$40,000.00	$45,085.00	$75,000.00	$109,000.00	$77,000.00
				$40,000.00	$45,085.00	$75,000.00	$109,000.00	$77,000.00
27	Miscellaneous Removal & Other Work	1	LS	$50,000.00	$209,992.00	$4,000.00	$40,000.00	$27,000.00
				$50,000.00	$209,992.00	$4,000.00	$40,000.00	$27,000.00
28	Uniformed, Off-Duty Law Enforcement Officer	1	LS	$25,000.00	$25,000.00	$25,000.00	$25,000.00	$25,000.00
				$25,000.00	$25,000.00	$25,000.00	$25,000.00	$25,000.00

29	Mobilization	1 LS	$100,000.00	$35,063.00	$119,400.00	$200,035.00	$27,000.00
			$100,000.00	$35,063.00	$119,400.00	$200,035.00	$27,000.00
30	Permit Fees	1 LS	$500.00	$500.00	$500.00	$500.00	$500.00
			$500.00	$500.00	$500.00	$500.00	$500.00
31	6" DIP Waterline and Fittings, Class 350, Furnish & Install (Restrained Joints)	155 LF	$75.00	$118.00	$100.00	$140.00	$74.00
			$11,625.00	$18,290.00	$15,500.00	$21,700.00	$11,470.00
		Total Base Bid:	***$2,433,280.00***	***$2,311,474.00***	***$2,385,100.00***	***$2,397,508.00***	***$2,671,051.50***