NOTE:
"BERRIDGE" CEE-LOCK PANELS (COPPER-COTE COLOR) - 24 GA. STANDING SEAM METAL ROOF

TYPICAL

10 GA METAL CLOSURE

4"X4"X3/16" T.S. FRAME

4"X3"X3/16" T.S. - SEE DETAIL #B

4"x3"x3/16" T.S. FRAME

3"X3"X3/16" T.S.

2'-8" N.T.S.

2'-8" N.T.S.

2'-8"

2'-9"

12" 12"

7½"

½" EXP JT. MATERIALS

TOP OF FIN SLAB

CONCRETE CLOSURE POUR ~ 3" MIN COVERAGE ALL STL

#4 VERTS @ 12" O.C. W/(1)-#5 HORIZ - SEE SECTION 'B'

A SECTION

NOTE:

UNDERSIDE OF METAL PANELS TO BE PAINTED DUN-EDWARDS #514 BONE CHINA. CONCEALED ANCHOR CUPS TO BE PRIMED BY G.C. PRIOR TO PAINTING.

SYMMETRICAL ABOUT ℄

24 GA RIDGE TRIM

4"X4"X3/16" T.S. RIDGE

10 GA BENT PL

4"X4"X3/16" T.S. FRAME

PROVIDE 2"X2" HAND-HOLE W/ COVER PLATE @ CENTER OF RIDGE TUBE - FOR FUTURE ELEC.

24 GA. STANDING SEAM METAL ROOF

12" 12"

4" 4"

8" 8"

10 GA. METAL CLOSURE

4"X4"X3/16" T.S. FRAME

TYP

16 GA PAINTED METAL PANELS TEMPE BRONZE - #B567 - T-104 - SHERWIN-WILLIAMS

4"X3"X3/16" T.S.

2"X2" HAND-HOLE @ LOCATIONS AS SHOWN (7 EACH VERT. SUPPORT)

3"X3"X3/16" T.S.

8'-0" N.T.S.

4" CONC SLAB ON 4" ABC - TYP

#4 VERTS @ 12" O.C. W/(1)-#5 HORIZ. SEE SECT 'A'

½" EXPANSION MATERIALS

EXISTING SIDEWALK

KICK PL ACCESS PANEL

CONCRETE CLOSURE POUR - 3" MIN COVERAGE ALL STL

1-1/2" 8"

6"

LANDSCAPE AREA

TURNDOWN @ SLAB EDGE

SEE PAGE 6 FOR ANCHOR BOLT DETAIL

B SECTION

APPROVED: _____ DEPUTY PUBLIC WORKS MANAGER CITY ENGINEER _____ DATE

APPROVED: _____ TRAFFIC ENGINEER _____ DATE

CITY OF TEMPE
PUBLIC WORKS DEPARTMENT

STANDARD BUS SHELTER
ROOF SECTIONS

ASSEMBLY DRAWING ONLY
SPECS AND DESIGN BY
REID & ASSOCIATES
TEMPE, AZ

DETAIL T-654
4 OF 12
REVISED 2007