R/W                C               R/W

(55'/65') ✱            (55'/65') ✱

(8') min.               (0.5')

VARIES (43.5') Min.      VARIES (43.5') Min.

S=0.015    Slope 0.025    Slope 0.025    S=0.015

1" Surface Course A-12.5

3" Asphaltic Concrete
Base Course A-25

Aggregate Base Course, thickness determined
by soils test and AASHTO "R" Value design
or from standard detail T-306 when indicated
by City engineer.

Sidewalk
Std. Detail No.230

Vertical Curb and Gutter
Std. Detail No.220 (7" C.F.)

# A-1 ARTERIAL STREET

✱ At Arterial/Arterial Intersection
(±300') Before Curb Return.

APPROVED: _____

CITY ENGINEER      DATE

CITY OF TEMPE
PUBLIC WORKS DEPARTMENT

ARTERIAL STREET CROSS-SECTION. (A-1)

DETAIL T-313

REVISED 2000